

NOTES:

- 1. 18-GAUGE, C-CHANNEL PRE-PUNCHED AND CUSTOM FORMED TO FIT SPECIFIED PROJECT REQUIREMENTS. SECURED TO WOOD BLOCKING, FASTEN WITH HP-FASTENERS @ 12" (305mm) O.C.
- 2. ALLOW 1/4" (6mm) MIN. TO 1/2" (13mm) MAX. SPACING BETWEEN CONSECUTIVE LENGTH OF C-CHANNELS. AT CORNERS, CUT C-CHANNEL TO PROVIDE MITERED JOINTS.
- 3. INSULATION WITH GREATER COMPRESSIVE STRENGTH OR WOOD BLOCKING.
- 4. REFER TO MR Z1.1 & MR Z1.2 AT THE END OF THIS SECTION.



